## **Project Summary**

## Commercial Property Dewitt, New York





## **Direct Push Services**

Boreholes were advanced with a track mounted Geoprobe<sup>™</sup> 6620DT rig using MC5 tooling. Twelve borings were made to approximately 8 feet below grade to collect continuous soil samples. Several of the borings were performed inside of the building and required penetrating a concrete floor.

## **Project Overview:**

As part of a potential real estate transaction an environmental investigation was required to evaluate potential impacts to the site from historical operations. Soil samples were collected from locations outside and inside of a building at the property.

Project Cost:

\$2,000

Project Duration:

1 day

• Project Completion Date:

August 2010

• Project Reference:

Confidential